

## Preliminary Draft of Program Summary Northeast Library

AREA	EXISTING	RENOVATION
<b>Building</b>		
Public Service Areas	Vestibule 196 sq. ft Lobby 589 sq. ft	To be determined
Meeting Room	1,368 sq. ft	Multi-use room
Staff work area	693 sq ft	Better work flow design, better ergonomic design
Total square footage	15,608 sq. ft.	15,608
Accessibility	Compliant; no special computer equipment or furnishings	Fully Compliant
<b>Site</b>		
Size of site	24,600 sq. ft.	24,600 sq. ft.
Parking spaces	24	24
<b>Collections</b>		
Adult books	30,236	Under review
Juvenile books	15,733	Under review
Teen books	3,177	Under review
Audiovisual materials	6,739	Under review
<b>Print and Audiovisual Total</b>	<b>55,885</b>	
World Language Collection (mixed format & audience)	800 450 adult 350 children	Under review
Magazines / Newspaper Subscriptions	115	Under review
<b>Public Service</b>		
Public computer workstations	14	50 +
Laptop Computers	0	6+
Distinct Teen area	No	Yes
Distinct Business area	No	Yes
Distinct Tech training area	No	Yes
Self-check machines	1	2
scanners	None	4
Assistive technology computers	0	2
Interior book drops	No	2
Seating: Table, carrel, and counter	26	60+
Seating: Lounge and bench	12	30+
Homework Helper station	1 station	1 expanded station
Meeting/Conference Rooms	1—78 person cap.	1 multi-purpose
Public Restrooms	2 multi-use	2 multi-use

<b>Facility Support Areas</b>		
Bookdrop room	Exterior bookdrop empties to janitor closet	Separate functional room
Automated Materials Handling	No	To be determined
Telecommunications room	No	Separate room
HVAC and controls	In need of replacement	new
Plumbing	Adequate for present building use	New fixtures, additional plumbing may be needed with renovation
Sprinklers	none	yes
<b>Sustainable Design Elements</b>		
Natural light	From East and South	Replace windows with low e glass, investigate additional natural light elements
Lighting Fixtures	Traditional	Operate on photocell Separate controls to minimize light usage
Flooring / carpeting	In need of replacement	Natural materials
Interior Signage	Unchangeable, outdated signage on stack ends, and inside library	Signage with replaceable elements to be modified by site staff
Green roof	No	To be determined
Storm-water run-off	Inadequate gutter system from roof, into street storm sewers	Possible rain garden catch-basin
Library Streetscape	Library set back from Central Avenue; inadequate, outdated exterior signage	More welcoming façade, orientation to the Avenue, updated exterior signage, possibly electronic
Landscaping	Some grass, trees along Central Avenue, no irrigation system	Attractive, low maintenance, low water usage, irrigation system, rain-garden for roof run-off